



X-HW 200

HOT WIRE POWER SUPPLY CALIBRATION

1. INTRODUCTION

This procedure is used to calibrate the control functions of X-HW 200, Hot Wire Power Supply System. This procedure applies to all AMET Hot Wire Power Supply Systems.

2. RESPONSIBILITIES

Performer	Responsibility
Technician	<p>After assuring the prerequisites have been met, performs Initial Setup using Section 4.1.</p> <p>Performs the following calibrations and linearity checks:</p> <ul style="list-style-type: none">▪ Frequency control per Section 4.2▪ Voltage control per Section 4.3▪ Voltage feedback per Section 4.4▪ Current feedback per Section 4.5▪ External voltage reference per Section 4.6▪ External voltage feedback per Section 4.7▪ External current feedback per Section 4.8. <p>Performs post calibration restoration of the Hot Wire Power Supply to return it to normal operational mode per Section 4.9.</p> <p>If calibration or linearity check fails, initiate troubleshooting with the assistance of AMET Technical Support.</p>

3. PREREQUISITS

Record the X-HW 200 Hot Wire Power Supply serial number in the Appendix A. The following tools and equipment are required by this procedure:

- 3.1. Digital Volt Meter (4-1/2-digit). Verify the meter is in calibration.
- 3.2. Calibrated DC Power Supply, 0 – 10 VDC
- 3.3. Miller Welding Power Load Bank, 3.75 KW @ 50 volts
- 3.4. RC filter constructed per Figure 1, *RC Filter Schematic and Connection* (See section 4.1.5.)
- 3.5. FLUKE Model 337 Clamp-On Meter (S/N 88111038)

X-HW 200

HOT WIRE POWER SUPPLY CALIBRATION

4. INSTRUCTIONS

4.1. Initial Setup

- 4.1.1. Remove all power from the Hot Wire Power Supply by disconnecting the main power connector on the back of the Hot Wire Power Supply.
- 4.1.2. Place the FLUKE clamp-on meter on the Work lead from the Hot Wire Power Supply.
- 4.1.3. Connect the load bank to the output of the Hot Wire Power Supply. (The output of the supply is an AC signal so the polarity does not matter.) Make sure that the load bank leads are connected properly and turn on the load bank.

NOTE

When measuring the power supply output voltage, use an RC filter circuit to eliminate erroneous readings caused by the switching noise of the power supply.

- 4.1.4. Connect the RC filter and voltmeter across the output leads of the Hot Wire Power Supply as shown in Figure 1. The meter will be parallel to the load bank. Set the meter to AC Volts on the 20 VAC range or Auto Range.

Figure 1, RC Filter Schematic and Connection



Resistor = 10k Ω , 1/2 W, 20%, carbon. Capacitor = 0.1 μ f, 50v.

NOTE

Perform steps 4.1.5 through 4.1.9 ONLY if performing a frequency calibration. Otherwise continue with step 4.1.10.

- 4.1.5. Remove the Hot Wire Power Supply cover by removing the appropriate screws.

X-HW 200

HOT WIRE POWER SUPPLY CALIBRATION

Effective Date: 04/09/2008

- 4.1.6. Remove the front cover of the Allen Bradley 1336 Plus II, Adjustable Frequency AC Drive by removing the locking screw on the bottom of the front panel of the drive.
- 4.1.7. Remove the blank Human Interface Module (HIM) blank panel located in the upper right quadrant of the Allen Bradley Drive enclosure.
- 4.1.8. Install the Allen Bradley HIM with the appropriate program. The HIM can be supplied by Allen Bradley but the program must be loaded to the HIM by technical personnel at AMET Inc.
- 4.1.9. Press and Hold the **Adjustment** Knob on the front of the Hot Wire Power Supply Control Panel while you connect the input power to the Hot Wire Power Supply. Hold the **Adjustment** Knob in until “Calibration 1.1” appears on the LCD display.
- 4.1.10. Using the **Adjustment** Knob scroll to “PID Control” and select it by pressing the **Adjustment** Knob. Scroll to “Cntl Loop” and change the value to “OFF” by pressing the **Adjustment** Knob.
- 4.1.11. Scroll to and select “Save & Exit.”

4.2. Frequency Control Calibration

Note

The Frequency Control has been calibrated at the factory. This function does not need to be recalibrated in the field. If you would like to verify the frequency calibration in the field then you will need to attach an oscilloscope across the output of the Hot Wire Power Supply and verify that the commanded frequency is accurate.

- 4.2.1. Select “Frequency Cntl” from the menu by scrolling through the menu using the **Adjustment** Knob and then pressing the **Adjustment** Knob to select the correct item.
- 4.2.2. Scroll to and select “Voltage SetPt” on the menu and enter 2.0 Volts in the value field.
- 4.2.3. Scroll to and enter 51 into the “Frequency” value field.
- 4.2.4. Press the **Contact** Button on the front of the Hot Wire Supply. This will command a 2.0 volt output at 51 hertz from the power supply.
- 4.2.5. Monitor the frequency display on the front of the HIM attached to the Allen Bradley Drive enclosure. If the display reads 51 hertz then continue with step 4.2.7. If the display does not read 51 hertz then continue with step 4.2.6.
- 4.2.6. Adjust the “Course Offset” and “Fine Offset” until the frequency displayed on the front of the HIM reads 51 hertz.
- 4.2.7. Scroll to and enter 299 in to the “Frequency” value field.
- 4.2.8. Monitor the frequency display on the front of the HIM that is attached to the Allen Bradley Drive. If the display reads 299 hertz then continue

X-HW 200 HOT WIRE POWER SUPPLY CALIBRATION

with step 4.2.10. If the display does not read 299 hertz then continue with step 4.2.9.

- 4.2.9. Adjust the “Course Gain” and “Fine Gain” until the frequency displayed on the front of the HIM reads 299 hertz.
- 4.2.10. Repeat steps 4.2.3 to 4.2.10 until no adjustments are needed.
- 4.2.11. Check the calibration of the Hot Wire Power Supply frequency control in 50 hertz increments starting at 50 hertz and ending at 300 hertz to confirm that the control is linear. Record the values in Appendix A, Table A-1, *Frequency Control Linearity Check*.
- 4.2.12. Press the **Contactor** Button on the front of the Hot Wire Supply to disable the output of the Hot Wire Power Supply.
- 4.2.13. Scroll down to and select the “Save and Exit” option of the “Frequency Cntl” menu by using the **Adjustment** Knob on the front of the Hot Wire Power Supply.
- 4.2.14. Remove power from the Hot Wire Power Supply by disconnecting the main power connector on the back of the Hot Wire Power Supply.

CAUTION

The Allen-Bradley Drive may remain energized for as long as one minute after removing power from the Hot Wire Power Supply. Be certain the Allen-Bradley Drive control panel LEDs are extinguished before proceeding.

- 4.2.15. Remove the HIM from the front of the Allen Bradley Drive and re-install the blank HIM panel.
- 4.2.16. Re-install the front cover of the Allen Bradley Drive and make sure that the locking screw is tight.
- 4.2.17. Re-install the Hot Wire Power Supply cover and make sure that all mounting screws are installed properly.
- 4.2.18. Press and Hold the **Adjustment** Knob on the front of the Hot Wire Power Supply Control Panel while you connect the input power to the Hot Wire Power Supply. Hold the **Adjustment** Knob in until “Calibration 1.1” appears on the LCD display.
- 4.2.19. If no other calibrations are to be completed, proceed to step 4.9. Otherwise, continue with the next calibration section.

4.3. Voltage Control Calibration Procedure

- 4.3.1. Set the load bank switches to 400 and 100. Do not change these settings during the remainder of the Voltage Control Calibration.
- 4.3.2. Select “Voltage Cntl” from the menu by scrolling through the menu using the **Adjustment** Knob and then pressing the **Adjustment** Knob to select the correct item.
- 4.3.3. Enter 2.0 Volts into the “Voltage SetPt” value field.



X-HW 200 HOT WIRE POWER SUPPLY CALIBRATION

- 4.3.4. Enter 60 into the “Frequency” value field. By setting this value to 60 hertz will allow the volt meter to make the most accurate measure of the voltage.
- 4.3.5. Press the **Contact** Button on the front of the Hot Wire Supply. This will command a 2.0 volt output from the power supply.
- 4.3.6. Check the digital volt meter connected in parallel to the load bank, to verify the actual output of the Hot Wire Power Supply.
- 4.3.7. If the Output of the Hot Wire Power Supply is incorrect then adjust the “Course Offset” and “Fine Offset” until the output reads 2.0 volts.
- 4.3.8. Enter 14.0 volts into the “Voltage SetPt” value field.
- 4.3.9. Check the digital volt meter, which is connected in parallel to the load bank, to verify the actual output of the Hot Wire Power Supply.
- 4.3.10. If the Output of the Hot Wire Power Supply is incorrect then adjust the “Course Gain” and “Fine Gain” until the output reads 14.0 volts.
- 4.3.11. Repeat steps 4.3.4 through 4.3.10 until no adjustments are necessary.
- 4.3.12. Check the output voltage of the Hot Wire Power Supply in 2 volt increments starting at 2.0 volts and ending at 14.0 volts to confirm that the output is linear. Record the values in Appendix A, Table A-2, *Voltage Control Linearity Check*.
- 4.3.13. Press the **Contact** Button on the front of the Hot Wire Supply to disable the output of the Hot Wire Power Supply.
- 4.3.14. Scroll down and select the “Save and Exit” option at the bottom of the “Voltage Control” menu by using the **Adjustment** Knob on the front of the Hot Wire Power Supply.
- 4.3.15. If no other calibrations are to be completed, proceed to step 4.9. Otherwise, continue with the next calibration section.

4.4. Voltage Feedback Calibration

- 4.4.1. Set the load bank switches to 400 and 100. Do not change these settings during the remainder of the Voltage Feedback Calibration.
- 4.4.2. Select “Voltage Fdbk” from the menu by scrolling through the menu using the **Adjustment** Knob and then pressing the **Adjustment** Knob to select this option.
- 4.4.3. Enter 2.0 Volts into the “Voltage SetPt” value field.
- 4.4.4. Press the **Contact** Button on the front of the Hot Wire Power Supply. This will command a 2.0 volt output from the power supply.
- 4.4.5. Check the “Volts” readout on the LCD Display on the front of the Hot Wire Power Supply to verify that it reads 2.0 volts.
- 4.4.6. If the readout on the LCD Display is incorrect then adjust the “Course Offset” and “Fine Offset” until the display reads 2 volts.
- 4.4.7. Enter 14.0 volts into the “Voltage SetPt” value field.
- 4.4.8. Check the “Volts” readout on the LCD Display on the front of the Hot Wire Power Supply to verify that it reads 14.0 volts.

**X-HW 200****HOT WIRE POWER SUPPLY CALIBRATION**

- 4.4.9. If the readout on the LCD Display is incorrect then adjust the “Course Gain” and “Fine Gain” until the display reads 14.0 volts.
- 4.4.10. Repeat steps 4.4.3 through 4.4.9 until no adjustment is necessary.
- 4.4.11. Check the calibration of the Hot Wire Power Supply voltage feedback in 2 volt increments starting at 2.0 volts and ending at 14.0 volts to confirm that the feedback is linear. Record the values in Appendix A, Table A-3, *Voltage Feedback Linearity Check*.
- 4.4.12. Press the **Contactor** Button on the front of the Hot Wire Supply to disable the output of the Hot Wire Power Supply.
- 4.4.13. Scroll down and select the “Save and Exit” option at the bottom of the “Voltage Fdbk” Menu by using the **Adjustment** Knob on the front of the Hot Wire Power Supply.
- 4.4.14. If no other calibrations are to be completed, proceed to step 4.9. Otherwise, continue with the next calibration section.

4.5. Current Feedback Calibration

- 4.5.1. Select “Current Fdbk” from the menu by scrolling through the menu using the **Adjustment** Knob and then pressing the Adjustment Knob to select this option.
- 4.5.2. Enter 2.0 Volts into the “Voltage SetPt” value field.
- 4.5.3. Press the **Contactor** Button on the front of the Hot Wire Supply and monitor the actual current output of the Hot Wire Power Supply using FLUKE clamp-on meter.
- 4.5.4. Adjust the “Voltage SetPt,” and if necessary reposition the load bank switches, until the actual current measured by the FLUKE clamp-on meter is 20 amps.
- 4.5.5. Check the “Current” readout on the LCD Display on the front of the Hot Wire Power Supply to verify that it reads 20 amps.
- 4.5.6. If the readout on the LCD Display is incorrect then adjust the “Course Offset” and “Fine Offset” until the display reads 20 amps.
- 4.5.7. Increase the “Voltage SetPt,” and if necessary reposition the load bank switches, until the actual current measured by the FLUKE clamp-on meter is 195 amps.
- 4.5.8. If the readout on the LCD Display is incorrect then adjust the “Course Gain” and “Fine Gain” until the display reads 195 amps.¹
- 4.5.9. Repeat steps 4.5.2 through 4.5.8 until no adjustment is necessary.
- 4.5.10. Check the calibration of the Hot Wire Power Supply current feedback in 25 amp increments starting at 20 amps and ending at 195 amps to confirm that the feedback is linear. Record the values in Appendix A, Table A-4, *Current Feedback Linearity Check*.
- 4.5.11. Press the **Contactor** Button on the front of the Hot Wire Supply to disable the output of the Hot Wire Power Supply.



X-HW 200

HOT WIRE POWER SUPPLY CALIBRATION

- 4.5.12. Scroll down and select the “Save and Exit” option at the bottom of the “Current Fdbk” Menu by using the **Adjustment** Knob on the front of the Hot Wire Power Supply.
- 4.5.13. If no other calibrations are to be completed, proceed to step 4.9. Otherwise, continue with the next calibration section.

4.6. External Voltage Reference Calibration

Note

This calibration procedure is only used for Hot Wire Power Supplies that will be connected to an AMET ADVENT System.

- 4.6.1. Select “External Ref” from the menu by scrolling through the menu using the **Adjustment** Knob and then pressing the Adjustment Knob to select this option.
- 4.6.2. Connect a 0-10 VDC variable power supply to pins D and E on the 16-pin Amphenol connector on the back of the Hot Wire Power Supply (D=Common; E=Positive).
- 4.6.3. Make sure that the 0-10 VDC variable power supply is turned off and check the “Voltage” readout on the LCD Display on the front of the Hot Wire Power Supply to verify that it reads 0.0 volts.
- 4.6.4. If the readout on the LCD Display is incorrect then adjust the “Course Offset” and “Fine Offset” until the display reads 0.0 volts.
- 4.6.5. Turn the 0-10 VDC variable power supply on and adjust to 10.0 volts.
- 4.6.6. Check the “Voltage” readout on the LCD Display on the front of the Hot Wire Power Supply to verify that it reads 20.0 volts. (There is a 2:1 ratio for this calibration procedure.)
- 4.6.7. If the readout on the LCD Display is incorrect then adjust the “Course Gain” and “Fine Gain” until the display reads 20.0 volts.
- 4.6.8. Repeat steps 4.6.3 to 4.6.7 until no adjustment is needed.
- 4.6.9. Check the calibration of the Hot Wire Power Supply External Voltage Reference in 1 volt increments starting at 0.0 volts and ending at 10.0 volts to confirm that the feedback is linear. Record the values in Appendix A, Table A-5, *External Voltage Reference Linearity Check*.
- 4.6.10. Scroll down and select the “Save and Exit” option at the bottom of the “External Ref” Menu by using the **Adjustment** Knob on the front of the Hot Wire Power Supply.
- 4.6.11. If no other calibrations are to be completed, proceed to step 4.9. Otherwise, continue with the next calibration section.



X-HW 200
HOT WIRE POWER SUPPLY CALIBRATION

Doc. No.: TP-HW-001

Revision: 3

Page: 8 of 13

Effective Date: 04/09/2008

4.7. Remote Voltage Feedback Calibration

Note:

This calibration procedure is only used for Hot Wire Power Supplies that will be connected to an AMET ADVENT System.

- 4.7.1. Select “Remote VFdbk” from the menu by scrolling through the menu using the **Adjustment** Knob and then pressing the Adjustment Knob to select this option.
- 4.7.2. Connect a calibrated volt meter to pins H and J on the 16-pin Amphenol connector on the back of the Hot Wire Power Supply (J=Common; H=Positive).
- 4.7.3. Enter 1.0 Volt into the “Voltage SetPt” value field.
- 4.7.4. Press the **Contact** Button on the front of the Hot Wire Supply.
- 4.7.5. Check the volt meter readout (connected to pins “J” and “H”) to verify it reads 0.5 volts. (There is a 2:1 ratio for this calibration procedure.)
- 4.7.6. If the readout on the voltmeter is incorrect then adjust the “Course Offset” and “Fine Offset” until the voltmeter reads 0.5 volts.
- 4.7.7. Enter 14.0 Volts into the “Voltage SetPt” value field.
- 4.7.8. Check the volt meter readout to verify that it reads 7.0 volts.
- 4.7.9. If the readout on the voltmeter is incorrect then adjust the “Course Gain” and “Fine Gain” until the voltmeter reads 7.0 volts.
- 4.7.10. Repeat steps 4.7.3 to 4.7.9 until no adjustment is needed.
- 4.7.11. Check the calibration of the Hot Wire Power Supply External Voltage Feedback in 2 volt increments starting at 2.0 volts and ending at 14.0 volts to confirm that the feedback is linear. Record the values in Appendix A, Table A-6, *Remote Voltage Feedback Linearity Check*.
- 4.7.12. Press the **Contact** Button on the front of the Hot Wire Supply to disable the output of the Hot Wire Power Supply.
- 4.7.13. Scroll down and select the “Save and Exit” option at the bottom of the “Remote VFdbk” menu by using the **Adjustment** Knob on the front of the Hot Wire Power Supply.
- 4.7.14. If no other calibrations are to be completed, proceed to step 4.9. Otherwise, continue with the next calibration section.



X-HW 200 HOT WIRE POWER SUPPLY CALIBRATION

4.8. Remote Current Feedback Calibration

Note

This calibration procedure is only used for Hot Wire Power Supplies that will be connected to an AMET ADVENT System.

- 4.8.1. Select “Remote CFdbk” from the menu by scrolling through the menu using the **Adjustment** Knob and then pressing the Adjustment Knob to select this option.
- 4.8.2. Connect a calibrated volt meter to pins F and G on the 16-pin Amphenol connector on the back of the Hot Wire Power Supply (G=Common; F=Positive).
- 4.8.3. Enter 2 Volts into the “Voltage SetPt” value field.
- 4.8.4. Press the **Contact** Button on the front of the Hot Wire Supply and monitor the actual current output of the Hot Wire Power Supply using the FLUKE clamp-on meter connected to the output of the Hot Wire Supply.
- 4.8.5. Adjust the “Voltage SetPt,” and if necessary reposition the load bank switches, until the actual current measured by the FLUKE clamp-on meter is 20 amps.
- 4.8.6. Check the volt meter readout to verify that it reads 1 volt. (There is a ratio of 20 amps per volt for this calibration procedure.)
- 4.8.7. If the readout on the voltmeter is incorrect then adjust the “Course Offset” and “Fine Offset” until the voltmeter reads 1.0 volts.
- 4.8.8. Increase the “Voltage SetPt,” and if necessary reposition the load bank switches, until the actual current measured by the FLUKE clamp-on meter is 200 amps.
- 4.8.9. Check the volt meter readout to verify that it reads 10.0 volts.
- 4.8.10. If the readout on the voltmeter is incorrect then adjust the “Course Gain” and “Fine Gain” until the voltmeter reads 10.0 volts.
- 4.8.11. Repeat steps 4.8.3 to 4.8.10 until no adjustments are needed.
- 4.8.12. Check the calibration of the Hot Wire Power Supply External Current Feedback in 20 amp increments starting at 20 amps and ending at 200 amps to confirm that the feedback is linear. Record the values in Appendix A, Table A-7, *Remote Current Feedback Linearity Check*.
- 4.8.13. Press the **Contact** Button on the front of the Hot Wire Supply to disable the output of the Hot Wire Power Supply.
- 4.8.14. Scroll down and select the “Save and Exit” option at the bottom of the “Remote CFdbk” menu by using the **Adjustment** Knob on the front of the Hot Wire Power Supply.
- 4.8.15. If no other calibrations are to be completed, proceed to step 4.9. Otherwise, continue with the next calibration section.



Doc. No.: TP-HW-001

Revision: 3

Page: 10 of 13

Effective Date: 04/09/2008

X-HW 200 HOT WIRE POWER SUPPLY CALIBRATION

4.9. Post Calibration Restoration

- 4.9.1. Once the Hot Wire Power Supply Calibration is complete you will need to perform the following tasks for the Power Supply to operate properly:
- 4.9.2. Using the **Adjustment** Knob select "PID Control". You will then need to highlight "PID LOOP" and change it to the "ON" option.
- 4.9.3. Scroll down and select the "Save and Exit" option on the menu by using the **Adjustment** Knob on the front of the Hot Wire Power Supply.
- 4.9.4. Cycle power to the Hot Wire Power Supply. This will place the Hot Wire Power Supply back into the correct operation mode.
- 4.9.5. Remove all power from the Hot Wire Power Supply by disconnecting the main power connector on the back of the Hot Wire Power Supply.
- 4.9.6. Turn off and disconnect the Miller Welding Power Load Bank.
- 4.9.7. Remove the RC Filter, voltmeter, FLUKE clamp-on meter and DC power supply. Return all equipment to its proper storage location.
- 4.9.8. Reinstall the Hot Wire Power Supply cover(s).
- 4.9.9. Attach a copy of the completed calibration to the unit.

5. RECORDS

The records for this calibration procedure comprise the calibration tables listed in Appendix A.

6. DEFINITIONS

None

7. REFERENCES

- 7.1. *X-HW 200 Hot Wire Power Supply Manual, SM-005 (DRAFT)*

8. APPENDIXES

- 8.1. Appendix A, Hot Wire Power Supply Calibration Data:
 - 8.1.1. Table A-1, *Frequency Control Linearity Check*
 - 8.1.2. Table A-2, *Voltage Control Linearity Check*
 - 8.1.3. Table A-3, *Voltage Feedback Linearity Check*
 - 8.1.4. Table A-4, *Current Feedback Linearity Check*
 - 8.1.5. Table A-5, *External Voltage Reference Linearity Check*
 - 8.1.6. Table A-6, *Remote Voltage Feedback Linearity Check*
 - 8.1.7. Table A-7, *Remote Current Feedback Linearity Check*



**X-HW 200
HOT WIRE POWER SUPPLY CALIBRATION**

APPENDIX A

X-HW 200 Hot Wire Power Supply Calibration Data

Technician

Date

Hot Wire Power Supply Serial Number

DC Power Supply Serial Number

Digital Voltmeter Serial Number

**Table A-1
Step 4.2.11 – Frequency Control Linearity Check**

Frequency Control Setting (Hz)	Frequency Control Indicated (Hz)	Expected Value (Hz)
50		48 – 52
100		98 – 102
150		148 – 152
200		198 – 202
250		248 – 252
300		298 - 302

**Table A-2
Step 4.3.12 - Voltage Control Linearity Check**

Voltage Control Setting (Volts)	Voltage Control Indicated (Volts)	Expected Value (Volts)
2.0		1.5 – 2.5
4.0		3.5 – 4.5
6.0		5.5 – 6.5
8.0		7.5 – 8.5
10.0		9.5 – 10.5
12.0		11.5 – 12.5
14.0		13.5 – 14.5



**X-HW 200
HOT WIRE POWER SUPPLY CALIBRATION**

Table A-3

Step 4.4.11 - Voltage Feedback Linearity Check

Voltage Feedback Setting (Volts)	Voltage Feedback Indicated (Volts)	Expected Value (Volts)
2.0		1.5 – 2.5
4.0		3.5 – 4.5
6.0		5.5 – 6.5
8.0		7.5 – 8.5
10.0		9.5 – 10.5
12.0		11.5 – 12.5
14.0		13.5 – 14.5

Table A-4

Step 4.5.10 - Current Feedback Linearity Check

FLUKE Current Feedback Setting (Amps)	Current Feedback Indicated (Amps)	Expected Value (Amps)
20.0		18.0 – 22.0
45.0		43.0 – 47.0
70.0		68.0 – 72.0
95.0		93.0 – 97.0
120.0		118.0 – 122.0
145.0		143.0 – 147.0
170.0		168.0 – 172.0
195.0		193.0 – 197.0

Table A-5

Step 4.6.9 - External Voltage Reference Linearity Check

Reference Voltage Setting (Volts)	Indicated Voltage (Volts)	Expected Value (Volts)
0.0		0.0 – 0.2
1.0		0.8 – 1.2
2.0		1.8 – 2.2
3.0		2.8 – 3.2
4.0		3.8 – 4.2
5.0		4.8 – 5.2
6.0		5.8 – 6.2
7.0		6.8 – 7.2
8.0		7.8 – 8.2
9.0		8.8 – 9.2
10.0		9.8 – 10.2



**X-HW 200
HOT WIRE POWER SUPPLY CALIBRATION**

Table A-6

Step 4.7.11 - Remote Voltage Feedback Linearity Check

Voltage Set Point Value (Volts)	Voltmeter Reading, Pin H to J (Volts)	Expected Value (Volts)
2.0		1.8 – 2.2
4.0		3.8 – 4.2
6.0		5.8 – 6.2
8.0		7.8 – 8.2
10.0		9.8 – 10.2
12.0		11.8 – 12.2
14.0		13.8 – 14.2

Table A-7

Step 4.8.12 – Remote Current Feedback Linearity Check

Input Set Point Values		Output Values
FLUKE Clamp-On Ammeter Indication (Amps)	Voltmeter Reading Pin F to G (Volts)	Expected Value (Volts)
20.0		0.8 – 1.2
40.0		1.8 – 2.2
60.0		2.8 – 3.2
80.0		3.8 – 4.2
100.0		4.8 – 5.2
120.0		5.8 – 6.2
140.0		6.8 – 7.2
160.0		7.8 – 8.2
180.0		8.8 – 9.2
200.0		9.8 – 10.2